

No	ELECTRICAL WORK	UNIT	2018, 3 rd QUARTER ELECTRICAL WORK DIRECT COST
1.1.3	C)Surface mounted distribution board of metal inclosure SDB-LP/GF/A with lockable door, complete with bus bar terminals 100A/3ph,neutral and earth bars, and consisting of :-		-
	1 pc main MCB of 80A/3ph		-
	1 pc RCD of 100mA/4pole		-
	6 pcs MCB of 10A/1ph		-
	2 pc MCB of 16A/1ph		-
	5 pc MCB of 25A/1ph		-
	2 pc MCB of 40A/3ph		-
	25% reserve pitches	set	67,771.59
			-
1.1.4	D)Surface mounted distribution board of metal inclosure SDB-LP/GF/B with lockable door, complete with bus bar terminals 100A/3ph,neutral and earth bars, and consisting of :-		-
	1 pc main MCB of 80A/3ph		-
	1 pc RCD of 100mA/4pole		-
	2 pcs MCB of 10A/1ph		-
	7 pc MCB of 16A/1ph		-
	2 pc MCB of 40A/3ph		-
	25% reserve pitches	set	84,624.40
			-
1.1.5	E) Flush mounted distribution board of metal inclosure SDB-SH1/GF = SDB-SH7GF with lockable door, complete with bus bar terminals 32A/1ph,neutral and earth bars, and consisting of :-		-
	1 pc main MCB of 25A/1ph, with 25A/1ph digital kilo watt meter		-
	1 pc RCD of 30mA/2pole		-
	1 pc MCB of 10A/1ph		-
	1 pc MCB of 16A/1ph		-
	25% reserve pitches	set	28,504.45
			-
1.1.6	F)Surface mounted distribution board of metal inclosure SDB-LP/1BF/A with lockable door, complete with bus bar terminals 32A/3ph,neutral and earth bars, and consisting of :-		-
	1 pc main MCB of 25A/3ph		-
	1 pc RCD of 30mA/4pole		-
	8 pcs MCB of 10A/1ph		-
	4 pc MCB of 16A/1ph		-
	25% reserve pitches	set	29,350.45
			-
1.1.7	G)Surface mounted distribution board of metal inclosure SDB-LP/1BF/B with lockable door, complete with bus bar terminals 40A/3ph,neutral and earth bars, and consisting of :-		-
	1 pc main MCB of 32A/3ph		-
	1 pc RCD of 30mA/4pole		-
	9 pcs MCB of 10A/1ph		-
	4 pc MCB of 16A/1ph		-
	3 pc MCB of 25A/1ph		-
	25% reserve pitches	set	34,084.45
			-

Mamush Lema



Henok Abebe



Hirut Ayalew

