

No	ELECTRICAL WORK	UNIT	2018, 3 rd QUARTER ELECTRICAL WORK DIRECT COST
1.1.8	I) Surface mounted distribution board of metal inclosure SDB-LP/2BF/A with lockable door, complete with bus bar terminals 32A/3ph, neutral and earth bars, and consisting of :-		-
	1 pc main MCB of 25A/3ph		-
	1 pc RCD of 30mA/4pole		-
	7 pcs MCB of 10A/1ph		-
	4 pc MCB of 16A/1ph		-
	25% reserve pitches	set	28,880.45
			-
1.1.9	K) Surface mounted distribution board of metal inclosure SDB-LP/3BF with lockable door, complete with bus bar terminals 32A/3ph, neutral and earth bars, and consisting of :-		-
	1 pc main MCB of 25A/3ph		-
	1 pc RCD of 30mA/4pole		-
	13 pcs MCB of 10A/1ph		-
	4 pc MCB of 16A/1ph		-
	25% reserve pitches	set	31,700.45
			-
1.1.10	L) Surface mounted distribution board of metal inclosure SDB-KCH/3BF with lockable door, complete with bus bar terminals 50A/3ph, neutral and earth bars, and consisting of :-		-
	1 pc main MCB of 40A/3ph		-
	1 pc RCD of 30mA/4pole		-
	4 pcs MCB of 10A/1ph		-
	7 pc MCB of 16A/1ph		-
	1 pc MCB of 20A/1ph		-
	1 pc MCB of 25A/1ph		-
	1 pc MCB of 20A/3ph		-
	25% reserve pitches	set	37,147.33
			-
1.1.11	M) Surface mounted distribution board of metal inclosure MDB-UPS with lockable door, complete with bus bar terminals 50A/3ph, neutral and earth bars, and consisting of :-		-
	1 pc main MCB of 40A/3ph		-
	1 pc RCD of 30mA/4pole		-
	3 pcs MCB of 16A/1ph		-
	8 pcs MCB of 20A/1ph		-
	2 pcs MCB of 25A/3ph		-
	25% reserve pitches	set	36,523.84
			-
1.1.12	N) Flush mounted distribution board of metal inclosure SDB-UPS/GF = SDB-UPS/3BF with lockable door, complete with bus bar terminals 32A/1ph, neutral and earth bars, and consisting of :-		-
	1 pc main MCB of 25A/1ph		-
	1 pc RCD of 30mA/2pole		-
	14 pcs MCB of 16A/1ph		-
	25% reserve pitches	set	28,114.45
			-

Mamush Lema



Henok Abebe



Hirut Ayalew

