

No	ELECTRICAL WORK	UNIT	2018, 3 rd QUARTER ELECTRICAL WORK DIRECT COST
1.1.13	O)Surface mounted distribution board of metal inclosure MDB-MP with lockable door, complete with bus bar terminals 500A/3ph,neutral and earth bars, and consisting of :-		-
	1 pc main MCCB of 400A/3ph		-
	1 pc RCD of 300mA/4pole		-
	1 pcs MCCB of 250A/3ph		-
	2 pcs MCCB of 63A/3ph		-
	3 pcs MCB of 40A/3ph		-
	25% reserve pitches	set	134,594.76
			-
1.1.14	P)Surface mounted distribution board of metal inclosure SDB-MP/1BF/A with lockable door, complete with bus bar terminals 80A/3ph,neutral and earth bars, and consisting of :-		-
	1 pc main MCCB of 63A/3ph		-
	1 pc RCD of 30mA/4pole		-
	7 pcs RCBO of 20A/3ph, Icu 6KA		-
	4 pcs RCBO of 32A/3ph, Icu 6KA		-
	25% reserve pitches	set	56,168.58
			-
1.1.15	Q)Surface mounted distribution board of metal inclosure SDB-MP/1BF/B with lockable door, complete with bus bar terminals 50A/3ph,neutral and earth bars, and consisting of :-		-
	1 pc main MCCB of 40A/3ph		-
	1 pc RCD of 30mA/4pole		-
	6 pcs RCBO of 20A/3ph, Icu 6KA		-
	2 pcs RCBO of 32A/3ph, Icu 6KA		-
	25% reserve pitches	set	51,553.84
			-
1.1.16	R)Surface mounted distribution board of metal inclosure SDB-MP/2BF/A with lockable door, complete with bus bar terminals 80A/3ph,neutral and earth bars, and consisting of :-		-
	1 pc main MCCB of 63A/3ph		-
	1 pc RCD of 30mA/4pole		-
	6 pcs RCBO of 20A/3ph, Icu 6KA		-
	4 pcs RCBO of 32A/3ph, Icu 6KA		-
	25% reserve pitches	set	63,326.85
1.1.17	U)Surface mounted distribution board of metal inclosure SDB-PUMP with lockable door, complete with bus bar terminals 320A/3ph,neutral and earth bars, and consisting of :-		-
	1 pc main MCCB of 250A/3ph		-
	1 pc RCD of 100mA/4pole		-
	2 pcs RCBO of 20A/3ph, Icu 6KA		-
	1 pc RCBO of 32A/3ph, Icu 6KA		-
	1 pc RCBO of 200A/3ph, Icu 6KA		-
	1 pc MCB of 16A/1ph		-
	1 pc MCB of 10A/1ph		-
	25% reserve pitches	set	104,081.72
			-

Mamush Lema



Henok Abebe



Hirut Ayalew

