

No	ELECTRICAL WORK	UNIT	2018, 3 rd QUARTER ELECTRICAL WORK DIRECT COST
1.1.18	W)Surface mounted distribution board of metal inclosure SDB-EV/GF with lockable door, complete with bus bar terminals 400A/3ph,neutral and earth bars, and consisting of :-		-
	1 pc main MCCB of 320A/3ph		-
	1 pc RCD of 100mA/4pole		-
	8 pcs MCB of 50A/3ph		-
	25% reserve pitches	set	107,293.59
1.1.19	X)Surface mounted distribution board of metal inclosure SDB-EV/1BF/A with lockable door, complete with bus bar terminals 630A/3ph,neutral and earth bars, and consisting of :-		-
	1 pc main MCCB of 500A/3ph		-
	1 pc RCD of 100mA/4pole		-
	12 pcs MCB of 50A/3ph		-
	25% reserve pitches	set	138,321.59
1.1.20	Y)Surface mounted distribution board of metal inclosure SDB-EV/1BF/B with lockable door, complete with bus bar terminals 320A/3ph,neutral and earth bars, and consisting of :-		-
	1 pc main MCCB of 250A/3ph		-
	1 pc RCD of 100mA/4pole		-
	6 pcs MCB of 50A/3ph		-
	25% reserve pitches	set	79,268.72
1.1.21	A-A)Surface mounted distribution board of metal inclosure SDB-EV/2BF/B with lockable door, complete with bus bar terminals 400A/3ph,neutral and earth bars, and consisting of :-		-
	1 pc main MCCB of 320A/3ph		-
	1 pc RCD of 100mA/4pole		-
	7 pcs MCB of 50A/3ph		-
	25% reserve pitches	set	101,400.72
1.1.21	A) Floor standing Factory made indoor distribution board with IP 44 with lockable door of hinged joints,including three phase bars of 800 Amp rating with separate neutral and earthing bars,connection and mounting accessories; complete with mounting rails for circuit breakers and labels to be made circuit numbers and spare spaces for future expansions of three modules minimum, TRI poles. All internal connections made in compliance with appropriate local and international standards to which references need to be made accordingly. and The distribution pillar shall be on the concrete pad with all necessary accessories Central Main Distribution Board, CMDB and consisting of :-		-
	1 pc main MCCB of 630A/3ph		-
	1 pc MCCB of 500A/3ph		-
	1 pc MCCB of 160A/3ph		-
	1 pc MCB of 50A/3ph		-
	1pc surge arrestor of 100KA		-
	3Pcs ammeters: 0-630A		-
	3Pcs current transformers: 630/5A		-
	1pc of voltmeter with selector switch (0-500V)		-
	with 4P+E busbar 800A		-
	1pc factory made drawing pocket and marking tags for all outgoing.all complete with 40% reserve spaces.	set	289,806.40

Mamush Lema

Henok Abebe

Hirut Ayalew