

No	ELECTRICAL WORK	UNIT	2018, 3 rd QUARTER ELECTRICAL WORK DIRECT COST
1.1.22	B) Floor standing distribution board of metal inclosure MDB-EV/1BF with lockable door, complete with bus bar terminals 1600A/3ph, neutral and earth bars, and consisting of :-		
	1 pc main MCCB of 1250A/3ph		
	1 pc RCD of 500mA/4pole		
	10 pcs MCB of 40A/1ph		
	10 pcs MCB of 50A/3ph		
	1 pc main MCCB of 250A/3ph		
	1 pc main MCCB of 500A/3ph		
	40% reserve pitches	set	524,460.40
1.1.23	Semi-Flush Mounted Distribution Board (SDB-PM)		
	Semi-Flush Mounted Distribution Board (SDB-PM)		
	1pcs 80A/3ph Main breaker		
	3pcs 40A/3ph		
	3pcs 32A/3ph		
	Bus Bar System (80A rated)		
	accessories	set	63,063.05
2.0	Light point		
2.1.1	Conductor (2x2.5mm ²) with 10 meter Average distance		
	PVC conduit 16mm		
	Junction Box		
	Connector	PCS	3,505.36
2.1.2	Conductor (3x2.5mm ²) with 10 meter Average distance		
	PVC conduit 16mm		
	Junction Box		
	Connector	PCS	4,546.66
2.1.3	Conductor (3x4mm ²) with 10 meter Average distance		
	PVC conduit 25mm		
	Junction Box		
	Connector	PCS	5,591.76
2.1.4	Conductor (3x4mm ²) with 10 meter Average distance		
	PVC conduit 50mm		
	Junction Box		
	Connector	PCS	6,287.46
3.0	Cable Installation Light point		
3.1.1	Power cable (3x4mm ²) with 10 meter Average distance		
	PVC conduit 25mm		
	Junction Box		
	Connector	PCS	5,727.06
3.1.2	Power cable (3x6mm ²) with 10 meter Average distance		
	PVC conduit 25mm		
	Junction Box		
	Connector	PCS	7,747.06
3.1.3	Power cable (5x4mm ²) with 10 meter average point length		
	PVC conduit 25mm		
	Junction Box		
	Connector	PCS	8,335.76

Mamush Lema

Henok Abebe

Hirut Ayalew