

No	ELECTRICAL WORK	UNIT	2018, 3 rd QUARTER ELECTRICAL WORK DIRECT COST
8.3.2	Panel LED 30x60 36W 3600lm If 30000hr 3000-4000k	PCS	3,425.87
8.3.3	Panel LED 60x60 48W 4800lm If 30000hr 3500-4000k	PCS	5,139.87
8.3.4	Panel LED 60x120 60W 6000lm If 35000hr 4000-6000k	PCS	5,445.61
8.4	<i>Led Flood Light (Pawza), korma</i>		
8.4.1	Led Flood Light (Pawza) 50w	PCS	1,695.65
8.4.2	Led Flood Light (Pawza) 100w	PCS	2,826.09
	Led Flood Light (Pawza)150w	PCS	3,869.57
8.4.3	Led Flood Light (Pawza) 200w	PCS	5,304.35
9.0	<i>Lightning Protection System</i>		
9.1.1	Early Streamer Emmision(ESE) Protector SI 40 to be mountied on top of the flood light pole of H=53m and all necessary connecting acessories.	PCS	142,733.50
9.1.2	Early Streamer Emmision(ESE) Protector SI 60 to be mountied on top of the flood light pole of H=53m and all necessary connecting acessories.	PCS	158,483.50
9.1.3	Early Streamer Emmision(ESE) Protector SI 70 to be mountied on top of the flood light pole of H=53m and all necessary connecting acessories.	PCS	158,483.50
	Early Streamer Emmision(ESE) Protector SI 125 to be mountied on top of the flood light pole of H=53m and all necessary connecting acessories.	PCS	174,233.50
9.1.4	16mm Air Termination circular galvanized steel rod 1.0m length	PCS	1,696.75
9.1.5	25 x 3mm insulated copper tape with vertical supportings every 1m to the pole & all the necessary accessories coordinate the routing of down conductors with the pole external skin and architectural features.	ml	1,158.73
9.1.6	1x70mm.sq galvanized Steel earth conductor ring as indicated on the drawing	ml	423.73
9.1.7	30x3.5mm galvanized steel ring earth termination net work.	ml	672.70
9.1.8	1500mm long and 50x50x3mm X-head galvanized steel earth rod including all connecting accessories.	PCS	3,061.33
9.1.9	Bonding materials for down conductor with air termination		
	Bonding materials to roof conductors holder		
	Bonding down conductor		
	Distance holders for earth termination	PCS	49,022.33

Mamush Lema

Henok Abebe

Hirut Ayalew