

IT.NO	DESCRIPTION	UNIT	2018 3rd Quarter (Only Direct cost)
5.39	8mm thick Chipwood wall with Eucalyptus dia.10cm and 5x7cm shashemene batten.	m ²	1,407.29
5.40	18mm thick Laminated MDF Wall with 5x7cm Shashemene batten wood work and all necessary work.	m ²	2,646.08
5.41	18mm thick Laminated MDF Wall. With out batten	m ²	1,755.36
5.43	20x20mm and 1.5mm thick Wire mesh wall Welded on the frame	m ²	1,093.10
5.44	Barbed wire fence with 40x40x3mm Angle Iron Frame	m ²	1,104.26
5.45	Supply & lay class A galvanized 800*1000*2.5cm hexagonal Mesh rock size 100- 250 for 1m³ as directed by the engineer. (ጋቢዮን በእጅ የተሰራ)	m ³	6,959.18
5.46	Supply & lay class A galvanized 800*1000*2.5cm hexagonal Mesh rock size 100- 250 for 1m³ as directed by the engineer. Fabricated (ጋቢዮን በማሽን የተሰራ)	m ³	7,159.18
6.00	Shear Wall for river side		
	R.C. C-25 378 kg of cement per m3		
6.10	C-25 Concrete (Mechanical Mix) 1:2:3 for Column ,shear wall	m ³	19,949.49
	R.C. C-30 420 kg of cement per m3		
6.20	C-30 Concrete (Mechanical Mix) 1:2:3 for Column ,shear wall	m ³	20,957.49
6.3	18mm thick Fair Faced Form work (high quality plywood) with crane	m ²	2,054.08

Prepared by:- Mulu Tafete.



Checked by:-Henok Abebe.



Approved by:- Hirut Ayalew.


