

ROAD WORK MAIN ITEMS

ITEM NO	DESCRIPTION	UNIT	2018 3rd QUARTER DIRECT COST
1	Capping layer under the sub base layer(Granular) compacted to thickness of 200mm up to average 15km distance.	m ³	2561.61
2	Gravel sub base compacted to 96% AACRA test S-11 Density (Compacted layer of maximum 150mm) up to average 15km.	m ³	4400.18
3	Base course compacted to 96% AACRA test S-11 Density (Compacted layer of maximum 150mm) up to average 15km.	m ³	4543.72

Prepared by/Checked by:- Henok Abebe




Approved by:-Hirut Ayalew

